# BRUHATH BENGALURU MAHANAGARA PALIKE

**Yelahanka Division, Yelahanka Zone**

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/05/2020-21 Dated: 03-09-2020

## APPROVED TENDER SCHEDULE –'B'

Item 20

Name of Work :--Improvements to roads and drains at Ambedkarnagara and Kanakanagara areas in ward no:04 of Yelahanka satellite town sub division

| Sl | Description | Unit | Approved Qty | Rate quoted by the contractor approved rates Sri G VENKATE GOWDA | |
|---|---|---|---|---|---|
| | | | | Rate | Rate in Words |
| 1 | Removing and refixing stone slabs of drains and pointing in CM (1:3) (P.No-27,I No-5.33) | Sqm | 234.00 | 116.81 | One Hundred Sixteen Paise EightyOne Only |
| 2 | KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications( I No-19.1, P No-143), 8km lead | Cum | 878.79 | 225.94 | Two Hundred TwentyFive Paise NinetyFour Only |
| 3 | Filling in foundation with granite/trap broken metal 100mm and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with lead up to 50m and lift 1.5m complete as per specifications. a) 40mm Jelly | Cum | 0.62 | 1995.10 | One Thousand Nine Hundred NinetyFive Paise Ten Only |
| 4 | b) 20mm Jelly | Cum | 0.62 | 1995.10 | One Thousand Nine Hundred NinetyFive Paise Ten Only |
| 5 | c) Coarse sand. | Cum | 0.47 | 2782.22 | Two Thousand Seven Hundred EightyTwo Paise TwentyTwo Only |
| 6 | d) Fine Sand | Cum | 0.31 | 2782.22 | Two Thousand Seven Hundred EightyTwo Paise TwentyTwo Only |
| 7 | e) 12.5mm chips | Cum | 0.47 | 1995.10 | One Thousand Nine Hundred NinetyFive Paise Ten Only |

| | | | | | |
|---|---|---|---|---|---|
| | , laying and jointing HDPE pipes ied grade and conforming to IS 995 with latest amendments and yingto work site including loading unloading at both destinations and ng and lowering into trenches, laying e to line and jointing of pipes and pecials, giving hydraulic test as per elevant ISS with all lead and lifts including encasing the pipe alround to a depth of not less than 15 cms. with soft gravel or selected earth available from the excavation, testing and commissioning. The rate is exclusive of required specials and fittings wherever necessary like saddle Tee, stub ends, flanged sets, bends, reducers etc. complete (Contractor will make his own arrangements for procuring water for testing) etc. for : HDPE Grade PE80-PN6.0, 630 mm dia. (Perforated Pipe for Rain Water Harvesting Pit) (BWSSB SR 2017-18, Pg No 121 Item No. 1.17 Code No. K010Q) | m | 9.00 | 11358.02 | Eleven Thousand Three Hundred FiftyEight Paise Two Only |
| 9 | Providing of Geonets for Rain Water Harvesting pit on top of the filter media as specified indrawings or as approved by Engineer Incharge. Data Rate | Sqm | 1.55 | 74.55 | SeventyFour Paise FiftyFive Only |
| 10 | KSRRB M2100-10. Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. (P.No-222,I No-27.18) | Cum | 142.65 | 5690.28 | Five Thousand Six Hundred Ninety Paise TwentyEight Only |

| | | | | | |
|---|---|---|---|---|---|
| | Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. With 20mm and sown size granite metal course aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compcted for walls and bottom including centring shuttering cost of material HOM of machinary curing etc., complete execluding cost of steel as per MORTH specification no. 1500, 1700, 2200 including cost of material labour HOM complete as per specification. (P.No.271, I.No.37.59.2 of PW, P&IWTD S.R 2018-19) | Cum | 399.65 | 7420.17 | Seven Thousand Four Hundred Twenty Paise Seventeen Only |
| 12 | KSRRB - M2300-14: Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, palcing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining memebrs wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.MORTH Specification No. 1600 & 2200 for TMT bars Fe 500. (P.No.239, I.No.29.29.2 of PW, P&IWTD S.R 2018-19) | Tonne | 29.97 | 77654.86 | SeventySeven Thousand Six Hundred FiftyFour Paise EightySix Only |
| 13 | Providing and Fixing pre cast covering Slab 100mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.As per Engineer incharge. (Data Rate) | Sqm | 501.00 | 2452.68 | Two Thousand Four Hundred FiftyTwo Paise SixtyEight Only |
| 14 | Providing and Fixing pre cast covering Slab 150mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.As per Engineer incharge. (Data Rate) | Sqm | 382.50 | 2616.40 | Two Thousand Six Hundred Sixteen Paise Fourty Only |

| | | | | | |
|---|---|---|---|---|---|
| | oviding and fixing RCC precast cover b of 250mm thick for drain in cement oncrete 1:1.5:3 using graded granite jelly 0mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate) | Sqm | 7.20 | 5686.19 | Five Thousand Six Hundred EightySix Paise Nineteen Only |
| 16 | Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete. As per the direction of Engineer incharge. (P.No.27, I.No.5.30) | Nos | 1824.00 | 453.89 | Four Hundred FiftyThree Paise EightyNine Only |
| 17 | Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 Specification No. KSRRB M800-6. (P.No.180, I.No.24.1 of PW, P&IWTD SR 2018-19) | Sqm | 246.30 | 89.00 | EightyNine Only |
| 18 | Providing and laying/fixing cement base, precast, pre polished cement concrete, designer tiles 25mm thick for flooring conforming to IS 1237 heavy duty tiles for flooring, treads of steps and landing, laid on a bed of 12mm thick cement mortar 1:3 mis finished with flush pointing using white cement, including cost of materials, mortar, including cutting, griding the edge to half/full round wherever required, labour, curing complete as per specification. (P.No-112,I No-14.62) | Sqm | 27.00 | 1370.56 | One Thousand Three Hundred Seventy Paise FiftySix Only |

| | | | | | |
|---|---|---|---|---|---|
| | KSRRB M300-53. Construction of embankment with approved material Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications, including cost of gravel / murrum, watering charges & compaction by vibratory roller to 95% of modified proctors density. MORTH Specification No. 305 (P.No.147, I.No.19.60) | Cum | 5.40 | 361.55 | Three Hundred SixtyOne Paise FiftyFive Only |
| 20 | Executive Bench- Made out of Sadarahalli grey stone with hand supports with 3 line finishing with arch design with 100mm slabs. Height 90x Length 1500 width 45 cms (Data approved rate) | Each | 10.00 | 19100.90 | Nineteen Thousand One Hundred Paise Ninety Only |
| 21 | Construction of granular sub-base Grading V as Sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite/ trap/basalt material, mixing in a mechanical mix plant at OMC, Carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98 % proctor density, complete as per specifications Clause 401 of MORTH V Revision.( I No-20.5,P No-153) | Cum | 171.60 | 2093.67 | Two Thousand NinetyThree Paise SixtySeven Only |
| 22 | KSRB 14.6 : Providing and laying heavy duty cobble stones interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM complete as per specifications.( I No-20.5,P No-153) heavy duty cobble stones 60mm thick | Sqm | 1144.00 | 1171.43 | One Thousand One Hundred SeventyOne Paise FourtyThree Only |

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.